

## अखिल भारतीय आयुर्वेद संस्थान

## ALL INDIA INSTITUTE OF AYURVEDA (AIIA,GOA)

(आयुष मंत्रालय, भारत सरकार के अंतर्गत स्वायत्त संस्थान)

(An Autonomous Organization under the Ministry of AYUSH, Govt. of India

## **QUOTATION INVITING TENDER**

Name of the work: Misc. works in lab and other area at AlIA Goa.

- 1. Sealed item rate quotations are invited for above said work.
- 2. The bidder shall submit the EMD of Rs.5,000.00 (Rs. Five Thousand Only) in form of Demand Draft/Bankers Cheque in favour of All India Institute of Ayurveda along with quotation document. For EMD Exemption please submit MSME/NSIC Certificate The quotation without EMD shall be rejected.
- 3. Estimated Cost id <u>Rs. 5,00,000.00</u> The work to be completed within 30 Days from the date of written instructions to carry out work.
- 4. The contractor should be **registered with GST**. Proof of registrations should be attached with quotation.
- 5. Quotation submitted without the EMD & GST registration certificate shall be rejected, whether they may be lowest
- 6. The all documents submitted shall be self attested with seal/stamp of firm/company.
- 7. All rates shall be quoted on the quotation form and shall include material, labour, transportation, all taxes & duties, supervision, tools, plants, wastage, sundries, scaffolding as required mobilization, demobilization, transportation etc. and nothing extra shall be payable on this account.
- 8. This quotation document shall be issued from the office of concerned department duly signed. The quotation document without signature shall be rejected.
- 9. Necessary deductions shall be made on account of statuary deductions as applicable.
- 10. The work shall be done as per Specifications mentioned in quotation document.
- 11. The sealed quotation so as to reach this office; Dean, All Indian Institute of Ayurveda, Village-Dhargal, Taluka -Pernem, MOPA, Airport Road, Goa-403513 on or before 24/05/2023 latest by 1500 hrs and submitted to Concerned Department. The quotation will be opened at 1530 Hours on the same day. The bidders may send their representative on opening of quotations.
- 12. The quantities given in schedule may vary as per actual variation at site.

M 21013

1

- 13. AIIA reserve the right to cancel the tender without assigning any reason thereof.
- 14. Tenderer are advised to inspect and examine the site and its surroundings and satisfy themselves before and inspect and examine the site and its surroundings and satisfy themselves before and inspect and examine the site and its surroundings and satisfy themselves before and its surroundings are successful. themselves before submitting their tender to the nature of the ground and sub-soil, the form and nature of the accommodation they m form and nature of the site, the means of access to the site, the accommodation they may require and in a site, the means of access to the site, the accommodation as to the risk, require and in general shall themselves obtain all necessary information as to the risk, contingencies and in general shall themselves obtain all necessary information as to the risk, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be tenderer shall be deemed to have full knowledge of the site, whether he inspects it or not and no extra all. and no extra charges consequent on any misunderstanding or otherwise shall be allowed.

For All India Institute of Ayurveda

I accept all the terms & Condition mentioned above.

Signature of Contractor with firm/Company Stamp

BIC1018 (08)

Name of the

	Name of the work: Misc. works in lal	and other a	area at AlL	A Goa	
S.NO Lab Work BOQ					
	ITEM	UNIT	QTY	RATE	AMOUNT
1.00	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in:				
-	Cement mortar 1:6 (1 Cement : 6 coarse sand)	Cum	3		
2.00	Providing of 18mm thick gang saw cut mirror polished premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups,including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				•
	Granite of any colour and shade				
	Area of slab over 0.5 sqm	Sqm	42		1
	Fixing of 18mm thick gang saw cut mirror polished premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups,including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				*
	Granite of any colour and shade Area of slab over 0.5 sqm				
	Area of slab over 0.5 squi	Sqm	30		

अर्थागम्य

4.0	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. (HORIZONTAL)			*	•
	Granite work	Metre	30		
5.00	Extra for fixing marble /granite stone over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive including cleaning etc. complete. (VERTICAL)	Metre	4	•	
6.00	Extra for providing opening of required size & shape for wash basins/ kitchen sink in kitchen platform, vanity counters and similar location in marble/Granite/stone work including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	2		
7.00	Providing and laying in position ready mixed M-25 grade concrete for reinforced cement concrete work, using fly ash and cement content as per approved design mix, and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work, including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering, finishing and reinforcement, including cost of admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. NOTE- (1) Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. (2) Fly ash conforming to grade I of IS 3812 (Part-1) only be used as part replacement of OPC as per IS: 456. Uniform blending with cement to be ensured in accordance				

<u> १</u>८०० १५५०

4

1	n the items of BMC and RMC.			
1	All works above plinth level upto floor V evel.	Cum	2	
1	Providing M-30 grade concrete instead of M-25 grade BMC/RMC.	Cum	10	
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.			
	Thermo - Mechanically Treated bars of grade 500D or more.	Kg	217	i ji
9	Centering and shuttering including strutting, propping etc.and removal of form for:			
	Suspended floors, roofs, landings, balconies and access platform with water proof ply 12 mm thick	SQM	32	
10.00	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	Sqm	108	
11.00	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete	Sqm	55	•
12.00				•
	New work (two or more coats) over and including water thinnable priming coat with cement primer	Sqm	122	
13	Supply and fixing of 6amp power point surface recessed medium class PVC casing, inclusive wiring with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and earthing with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. with modular switch, modular plate, suitable PVC box as required.	NOS	15	•

DICINISTO

	Providing of 18mm thick gang saw cut mirror polished premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups,including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
F	Granite of any colour and shade  Area of slab over 0.5 sqm	Sqm	4.00		
		Sqiii		Total	
			•	GST 18 %	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
				Greand Total	

Rupees	 	only-
•		

(Rate should be quoted in words and in figure both)

Signature of Contractor with Seal of firm/company.

30/21/110/2